

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6131
Name: Drillers & Producers, Inc.
Address 1: P.O. Box 385
Address 2: _____
City: Newton State: Ks Zip: 67114 + _____
Contact Person: Bill Hanson
Phone: (316) 841-0022
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Mississippi Depth to Top: 2367 Bottom: 2377 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 115-21051-001
Spot Description: _____
SE SE NE Sec. 8 Twp. 22 S. R. 4 East West
280 2984 Feet from North / South Line of Section
32 411 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Marion
Lease Name: Speir Well #: 4
Date Well Completed: 11-2-85
The plugging proposal was approved on: 12-30-10 (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 12-30-10
Plugging Completed: 12-30-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	oil/water	surface	8 5/8"	207'	0
		casing	4 1/2"	2407'	1000'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2367' pumped 50 sacks class A 3% cc, 3/4 lb per sack poly, displaced with 10 bbl water, pulled tubing, taged cement with wire line at 2110'. Shot casing off at 1000' pulled and cemented top from 290' to surface with 151 sacks class A

Plugging Contractor License #: 5870 Name: Phillips Well Service Inc.
Address 1: P.O. Box 1263 Address 2: _____
City: El Dorado State: Ks Zip: 67042 + _____
Phone: (316) 321-6650
Name of Party Responsible for Plugging Fees: Drillers & Producers Inc.
State of Kansas County, Harvey, ss.
William Hanson Employee of Operator or Operator on above-described well.
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Will Hanson

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JAN 13 2011
KCC WICHITA