


15-195-00295-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Trego County. Sec. 14 Twp. 13 Rge. - (E) 22 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 330' from South & 990'  
Lease Owner Continental Oil Co. from East lines of Section  
Lease Name W. D. Caskey Well No. 1  
Office Address Drawer 1267 - Ponca City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 9-3 19 54  
Application for plugging filed 9-3 19 54  
Application for plugging approved 9-3 19 54  
Plugging commenced 9-3 19 54  
Plugging completed 9-3 19 54  
Reason for abandonment of well or producing formation No commercial zones  
encountered.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? YES

Name of Conservation Agent who supervised plugging of this well Mr. Elden Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4389 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Conglomerate	Show of oil and water.	4067	4090	8 5/8"	247	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 220'. Set plug at 220'. Dumped 20 sacks of cement on plug. Set plug at 40' and dumped 1/2 sack of hulls and 10 sacks of cement on plug to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohmann-Johnson Drilling Co., Inc.  
Address 320 Indiana Bank Building  
Evansville, Indiana

STATE OF Kansas COUNTY OF Barton ss.  
F. L. Dunn (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ARC  
9-7-54 ✓  
State Corp. Comm. - RFD - File  
(Signature) [Signature]  
Drawer 161, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of September, 19 54.



July 30, 1958  
PLUGGING  
FILE SEC 14 T 13 R 22W  
BOOK PAGE 41 LINE 45

O. E. Jones  
RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 9 1954  
09-09-54  
CONSERVATION DIVISION  
Wichita, Kansas  
Notary Public.

15-195-00295-00-00

W. D. CASKEY NO. 1  
Section 14-Twp 13S-R-22W  
Trego County, Kansas

WELL RECORD

Operator: Continental Oil Company  
Ponca City, Oklahoma

Contractor: Lohmann-Johnson Drilling Co., Inc.  
320 Indiana Bank Building  
Evansville, Indiana

Casing: Ran 6 Jts. 8-5/8" Surface Pipe set @ 247' W/150 Sacks

Started: August 19, 1954  
Completed: September 4, 1954

L O G

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
0	60	Shale
60	70	Sand
70	760	Shale
760	1000	Shale & Sand
1000	1150	Red Bed
1150	1450	Sand
1450	1580	Shale
1580	1600	Shale & Red Bed
1600	1650	Sand
1650	1705	Red Bed
1705	1750	Anhydrite
1750	1920	Shale & Shells
1920	2220	Shale & Lime
2220	2400	Shale & Shells
2400	2520	Shale & Lime
2520	2700	Lime & Shale
2700	2885	Shale & Lime
2885	3085	Shale
3085	3428	Shale & Lime
3428	3645	Lime & Shale
3645	3755	Lime
3755	3800	Lime & Shale
3800	3894	Lime
3894	3987	Lime & Shale
3987	4017	Shale & Lime
4017	4090	Lime & Shale
4090	4150	Chert, Lime & Shale
4150	4166	Chert
4166	4195	Shale, Lime & Chert
4195	4232	Shale & Chert
4232	4260	Chert, Dolomite & Shale
4260	4267	Lime - Chert
4267	4303	Lime & Shale
4303	4353	Lime, Shale & Chert
4353	4387	Lime & Chert
4387	4389	Lime
4389		TOTAL DEPTH

Dry & Abandoned  
Plugged as of September 4, 1954

9-10-54  
State Corp. Comm. - SRC - RFD - File

**PLUGGING**  
FILE SEC 14 T 13 R 22W  
BOOK PAGE 61 LINE 45