


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-195-20432-00-00
Form CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 11 Twp. 13 Rge. (E) 22 (W)
Location as "NE/CNW/SW" or footage from lines SW-SW-SE
Lease Owner Weilert & Parker
Lease Name Armbruster Well No. 1
Office Address P. O. Box 726 Hays, Kansas 67601
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 7 19 77
Application for plugging filed (oral) Oct. 7 19 77
Application for plugging approved Oct. 7 19 77
Plugging commenced Oct. 7 19 77
Plugging completed Oct. 7 19 77
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Baltazor
Producing formation Depth to top Bottom Total Depth of Well 3842 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	161	8 5/8"	x	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st. plug at 700 feet with 70 sacks cement 50-50 poz. 6% gel.
2nd. plug at 150 feet with 20 sacks cement 50-50 poz. 6% gel.
3rd plug at 40 feet with 10 sacks cement 50-50 poz. 6% gel.

RECEIVED
OCT 12 1977
10-12-77
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sun Oilwell Cementing
Address P.O. Box 169 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Graham, ss.
Jerry M. Helberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry M. Helberg
Box 32 Morland, Kansas 67650
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of Oct., 19 77

My commission expires 12-4-79



Notary Public.

15-195-20432-00-00

DRILLERS LOG

ARMBRUSTER #1

CASING RECORD:

8 5/8" set at 161'

TOTAL DEPTH:

3842'

OPERATOR: Weilert & Parker

CONTRACTOR: Helberg Oil Company

COMMENCED: September 27, 1977

COMPLETED: October 7, 1977

DESCRIPTION:

SW SW SE
Sec. 14-13-22, Trego County, Kansas

FORMATION	FROM	TO	REMARKS
Sand & Shale	0	179	
Sand & Shale	179	490	
Shale	490	1429	
Sand & Shale	1429	1724	
Anhydrite	1724	1753	
Anhydrite	1753	1764	
Sand & Shale	1764	2078	
Shale	2078	2380	
Shale	2380	2494	
Sand & Shale	2494	2596	
Shale	2596	2690	
Shale	2690	2775	
Shale	2775	2875	
Shale	2875	2976	
Shale	2976	3060	
Shale & Shells	3060	3152	
Shale	3152	3245	
Shand & Shale	3245	3337	
Sand & Shale	3337	3430	
Shale	3430	3520	
Shale	3520	3595	
Shale	3595	3597	
Hebner	3597	3601	
Shale & Lime	3601	3654	
Shale & Lime	3654	3700	
Lime	3700	3742	
Lime	3742	3791	
Lime	3791	3842	
T.D.	3842		D & A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

HELBERG OIL COMPANY

Jerry M. Helberg
Jerry M. Helberg

Subscribed and sworn to before me this 11th day of October, 1977.

Faye E. Minium
Notary Public

My commission expires _____

