

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Benson #1	
NW-NW-Se,	
Sec. 21-13S, 22W,	
Trego County, Ks.	
-	
-	
-	

Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

15-195-00202-00-00

Trego County. Sec. 21 Twp 13S Rge. 22 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW-NW-SE
Lease Owner Leo Dreiling & etal
Lease Name Benson Well No. #1
Office Address Hays, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-7 19 51
Application for plugging filed 11-7 19 51
Application for plugging approved 11-7 19 51
Plugging commenced 11-7 4:00 P.M. 19 51
Plugging completed 11-7-12:00 P.M. 19 51
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4330 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sail, shale, shells		0	210'	8 5/8"	210'	none
KC.		3744'	4299'		Dry	Dry
Arbuckle		4299'	4330'		Dry	Dry

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Stirred pits, filled hole with heavy mud. Placed wood plug and 1/2 sacks hull at 200 feet. Ran 15 sacks of cement on same. Filled hole with heavy mud to 40 feet. Placed wood plug at 40 feet 1/2 sack hulls, and 10 sacks of cement, filling to bottom of cellar.

NOV 26 1951
11-26-51
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Strain Drilling Company
Address Box 188, Hays, Kansas.

STATE OF Kansas, COUNTY OF Ellis, ss.
T.C. Strain (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 188, Hays, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 10 day of November, 1951.

My commission expires

23-3273-s 4-50-10M

PLUGGING
FILE SEC 21 T 13 R 22 W
BOOK PAGE 24

WELL LOG

COMPANY: Leo Dreiling & etal

LEASE: Benson # 1

15-195-00202-00-00

NW-NW-SE, Sec. 21
Twp. 13, Rge. 22W
Trego County, Ks.

ELEVATION: 2351 R.B.

Note: All meas. rotary Bushings.

0	208 Soil, shale shells
208	515 Shale
515	550 Shale & Gray Lime
550	745 Shale
745	1250 Shale
1250	1370 Shale
1370	1570 Sand
1570	1710 Shale & Shells
1710	1835 Shale & redbed
1835	1860 Anhydrite
1860	1980 Shale & Shells
1980	2160 Shale
2150	2345 Shale & Lime
2345	2485 Shale
2485	2655 Shale & Lime
2655	2780 Shale & Lime
2780	2840 Shale
2840	2930 Shale
2930	3065 Shale
3065	3135 Shale
3135	3220 Shale & Lime
3220	3280 Shale
3280	3365 Shale
3365	3470 Shale & Lime
3470	3540 Lime & Shale
3540	3592 Shale & Lime
3592	3645 Shale & Lime
3645	3690 Lime
3690	3725 Shale & Lime
3725	3765 Lime
3765	3783 Lime
3783	3825 Lime
3825	3865 Lime
3865	3910 Lime
3910	3917 Lime
3917	3950 Lime
3950	4010 Lime & Shale
4010	4050 Shale & Lime
4050	4085 Lime
4085	4125 Lime
4125	4150 Lime
4150	4190 Lime
4190	4230 Lime & Shale
4230	4291 Lime & Shale
4291	4315 Lime
4315	4330 Lime
4330	T.D. (R.B. Meas.)

TOPS:

Anhydrite	1835	Ch. Cong.	4201
Heebner	3711,	Arbuckle	4299
K.C.	3744	T.D.	4330

D.S.T. By Johnston Testing Co.

3917 Tool open 30 min. Recovered
7 foot slightly oil cut mud. B.H.P.
15 min. -0 Press.

Ran Schlumberger to Total Depth.

COMMENCED: 10-24-51
COMPLETED: 11-7-51

CASING RECORD:

8 5/8" Surface Casing set at 210'
w/140 sks cement. By Sun Cementing
Company.STATE OF KANSAS) SS
COUNTY, OF ELLIS)I hereby confirm that the above and foregoing is a true and
correct copy of the log of the Benson # 1, located NW-NW-SE, Sec. 21,
Twp. 13, Rge. 22W, Trego County, Kansas.CONTRACTOR: STRAIN DRILLING COMPANY

BY

T.C. Strain

Subscribed and sworn to me before this 10 day of November, 1951
My Commission expires July 18, 1955.Dolores Ann Pais
NOTARY PUBLIC.