

15-195-00091-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Trego County, Sec. 15 Twp. 13 Rge. 22W (E) (W)
Location as "NE/CNW&SW%" or footage from lines SE SE SE
Lease Owner Hellar Drilling Company, Inc.
Lease Name Shaffer Well No. 1
Office Address 1014 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 7-29 19 59
Application for plugging filed 7-29 19 59
Application for plugging approved 7-29 19 59
Plugging commenced 7-29 19 59
Plugging completed 7-29 19 59
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, Orally

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	255'	8-5/8"	265.62'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug at 600' w/20 sacks cement. 2nd plug at 180' w/15 sacks cement and top plug at 40' w/10 sacks cement to bottom of cellar.

*RCW
08-05-59*

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 1014 Union Center

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. D. L. Hellar, President of _____ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar
1014 Union Center
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of July, 19 59
Wanda Lou Bruce
Notary Public.
My commission expires March 6, 1961.

PLUGGING
FILE SEC 15 T 13 R 22W
BOOK PAGE 58 LINE 44

15-00091-00-00

WELL LOG

OWNER:
LEASE:
LOCATION:

COMMENCED:
COMPLETED:
CASING:

HELLAR DRILLING COMPANY, INC.
SHAFFER #1
SE SE SE, SEC. 15-13S-22W
TREGO COUNTY, KANSAS
JULY 20, 1959
JULY 29, 1959
SET 8-5/8" @ 255' w/135 sacks
cement.

		<u>LOG TOPS</u>
0 - 242	Surface clay	Elevation 2295 K.B.
242 - 490	Shale	Anhydrite 1745 / 550
490 - 1495	Dakota sand & shale	Base/Anhydrite 1785 / 510
1495 - 1535	Anhydrite	Topeka 3390 -1095
1535 - 2310	Shale	Heebner 3636 -1341
2310 - 3090	Lime & Shale	Toronto 3654 -1359
3090 - 3365	Shale & lime	Lansing 3670 -1375
3365 - 3599	Lime & shale	Base/Kans.City 3920 -1625
3599 - 3646	Shale & lime	Marmaton Lime 3998 -1703
3646 - 3760	Lime	Ft. Scott 4084 -1789
3760 - 3776	Cherty lime	Sandy Conglomerate 4102 -1807
3776 - 3918	Lime	Cherty Conglomerate 4199-1904
3918 - 3967	Lime & Shale	
3967 - 4040	Conglomerate	
4040 - 4136	Cherty lime	
4136 - 4190	Conglomerate	
4190 - 4200	Arbuckle	
4200	RTD - D & A	

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the SHAFFER #1, located in the SE SE SE of Section 15, Twp. 13S, Rge. 22W, Trego County, Kansas, as reflected by the files of the HELLAR DRILLING COMPANY, INC.

HELLAR DRILLING COMPANY, INC.

BY D. L. Hellar
D. L. Hellar, President

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5th day of August, 1959.

Wanda Lou Bivins
Notary Public



My commission expires March 6, 1961.

RECEIVED
STATE DEPARTMENT COMMISSION
AUG 7 1959
COMMISSION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 15 13 R 22W
BOOK PAGE 58 LINE 44