

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21289-00-00
Spot: SWSENWNW Sec/Twnshp/Rge: 13-24S-17W
4157 feet from S Section Line, 4436 feet from E Section Line
Lease Name: HAWLEY Well #: 9-13
County: EDWARDS Total Vertical Depth: 4450 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	330		WITH 225 SX CMT
PROD	4.5	4441	2240	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4210' & 4 SX CMT. PLUG AT 1110' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2010 10:35 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4210' & 4 SX CMT. 1ST PLUG AT 1110' WITH 15 SX GEL - 50# HULLS - 50 SX CMT. 2ND PLUG AT 360 WITH 50 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4300	4337		
4268	4300		

INVOICED

DATE _____

INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Richard W. Lacey

(TECHNICIAN)

RECEIVED
SEP 24 2010
KCC DODGE CITY

RECEIVED
SEP 30 2010
KCC WICHITA

Form CP-2/3