

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22969-00-00
Spot: S2SENV Sec/Twnshp/Rge: 17-21S-11W
2970 feet from S Section Line, 3300 feet from E Section Line
Lease Name: KEELER Well #: 3-17
County: STAFFORD Total Vertical Depth: 3600 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	278		WITH 225 SX CMT
PLG		3460		
PROD	5.5	3595	2180	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2010 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 3350' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/09/2010 2:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3330' & 5 SX CMT WITH A DUMP BAILER. 1ST PLUG AT 603' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 315' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3471	3479		ARBUCKLE
3416	3420		SIMPSON SAND

INVOICED

DATE _____

INV. NO. _____

RECEIVED

AUG 17 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

KCC WICHITA

Plugged through: CSG

District: 01

Signed Richard Mc Lacey
(TECHNICIAN)

RECEIVED
AUG 11 2010
KCC DODGE CITY

Form CP 2/3