

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12583-00-00
Spot: N2SESWSE Sec/Twnshp/Rge: 17-21S-11W
600 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SMITH C Well #: B3-17
County: STAFFORD Total Vertical Depth: 3430 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	317		WITH 175 SX CMT
PROD	5.5	3415	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2010 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3300' & 5 SX CMT. PERFORATE 5 1/2" @ 600'. RUN TBG TO 600' & CIRCULATE CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. PULL TBG & TOP OFF HOLE WITH CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2010 12:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3280' & 5 SX CMT WITH DUMP BAILER. PERFORATED 5 1/2" @ 600'. RAN TBG TO 620'. PUMPED 200 SX CMT DOWN TBG. CIRCULATED CMT UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS TO SURFACE. PULLED TBG OUT OF HOLE. TOPPED OFF HOLE WITH 15 SX CMT.

Perfs:

INVOICED

DATE _____
INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

RECEIVED
AUG 17 2010
KCC WICHITA

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
AUG 11 2010
KCC DODGE CITY

Form CP 2/3