

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20782-00-00
Spot: NENWNE Sec/Twnshp/Rge: 26-13S-30W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BEOUGHER Well #: 1
County: GOVE Total Vertical Depth: 4500 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	326	0	220 SX
PROD	5.5	4494	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2010 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION, INC. Phone: (785) 483-1559

Proposed Plugging Method: Ordered 420 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel.
DV Tool at 2185' w/400 sxs cement.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/26/2010 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

08/23/2010 - Ran tubing to 4207' - pumped 14 sxs gel - followed with 50 sxs cement with 200# hulls.
Pulled tubing to 2650' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1650' - pumped 165 sxs cement - good circulation of cement.
Pulled tubing out - tied onto backside - squeezed with 180 sxs cement - no pressure - ran out of cement.
Backside standing full of cement. Will come back and top off the 5 1/2" in a couple of days.
08/26/2010 - Pumped 50 sxs cement with 300# hulls down the casing - full - done.

Perfs:

Top	Bot	Thru	Comments
4488	4492		JOHNSON
4408	4428		FT SCOTT
4388	4392		MYRICK ST

INVOICE


DATE _____
INV. NO. _____

Remarks: ALLIED CEMENTING COMPANY-TICKET #38985.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

(M)

RECEIVED

AUG 30 2010

Form CP-2/3

KCC WICHITA

AUG 27 2010

RAINS & WILLIAMSON
OIL COMPANY, INC.
435 PAGE COURT
WICHITA, KS 67202

5146

#1 BEOUGHER

26-13-30W
NE NW NE

CONTR COMPANY TOOLS CTV GOVE
FIELD GOVE EXT (1/8 W)
GEOLOGICAL

+	+
+	+
+	+
+	+

ELV 2886 KB SPD 7/20/84 CARD ISSUED 10/4/84 IP P 150 BO & 47 BWPD
2877 GL CHER (JH ZN) 4494.5-4495
(NEW PAY)

SMP	Tops	Depth/Datum	API 15-063-20,782
ANH	2298+	588	8 5/8 " 326/220SX, 5 1/2 " 4494.5/100SX
B/ ANH	2333+	553	DST (1) 3884-3950 (TOR, LANS A) / 30-30-30-30, (1ST OP) WB, DIED/ 18", (2ND OP) NB, REC 130' WM, SIP 1045-1004#, FP 31-31 / 74-74#, HP 1947-1926#, BHT 115°
HEEB	3885-	999	
TOR	3898-	1012	DST (2) 3944-94 (LANS B&D) / 30-30-30-30, (1ST OP) VERY WB, (2ND OP) VERY WB, DIED/ 5", REC 190' MW, SIP 993-983#, FP 52-62 / 95-95#, H- 1957-1926#
LANS	3922-	1036	
STARK	4145-	1259	DST (3) 3994-4014 (LANS E&F) / 30-30-30-30, (1ST OP) VERY WB, (2ND OP) NB, REC 10' MW, SIP 1077-1077#, FP 10-10 / 31-31#, H- 1957-1947#, BHT 120°
BKC	4218-	1332	
MARM	4240-	1354	DST (4) 4124-48 (LANS J) / 30-30-30-30, (1ST OP) VERY WB/ DIED 1", (2ND OP) NB, 2'M, SIP 10-10#, FP 10-10 / 10-10#, HP 2000-1958#, BHT 124°
PAW	4334-	1448	
*FT SC	4406-	1520	MICT - CO, PF (JH ZN), 4488-92, W/ 2 SPF, PULLED 15GF (10% OIL) / 1ST 30", 2ND PULL 10GF (10% OIL), AC 1000G, ONFU 200' OILY MUD, SQZ'D PFS W/ 100SX CMT, DO CMT, SWB HOLE DRY, (over)
*CHER	4437-	1551	
*JH ZN	4485-	1599	
*RTD<D	4495-	1609	
* LOG TOPS			

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

RAINS & WILLIAMSON
OIL COMPANY, INC.

#1 BEOUGHER

26-13-30W
NE NW NE

AC (JH ZN OH), W/ 100G, SWB 3000' FROM SURF, GSO, REC 10BF (38% OIL) / 1ST PULL, 10BF (44% OIL) / 2ND PULL, 10BF (57% OIL) / 3RD PULL, MADE 3 MORE PULLS, REC 16.83 BF (56% OIL), SI/ 30", SWB DWN, REC 6.20 BF (90% OIL) / 30" PULL, 8.25 BF (86% OIL) / 2ND 30", 9 BF (90% OIL) / 3RD 30", ONFU 3000' FL, SWB 16 BF (100% OIL) / 1 HR, SWB 7.14 BO / 1ST HR, 7.75 BO / 2ND HR, 8.95 BO / 3RD HR, 8.25 BF (95% OIL) / 30" PULL, T&R, POP, P 150 BO & 47 BWP, 9/17/84