

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24244-00-00  
Spot: SESWSWSW Sec/Twnshp/Rge: 5-16S-22W  
293 feet from S Section Line, 439 feet from W Section Line  
Lease Name: JANET SUE Well #: 1-5  
County: NESS Total Vertical Depth: 4434 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 125 N MARKET STE 1252  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	237		WITH 160 SX CMT
DVT		1760		
PROD	5.5	4429	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2010 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PUMP GEL SPACER & CMT FORM 1760'-0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/22/2010 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT, THEN 23 SX GEL & 170 SX CMT. CMT TO SURFACE. MAXIMUM PRESSURE 2000#. SHUT IN PRESSURE 300#. TIED ONTO BACKSIDE & PUMPED 1/4 BBL. PRESSURE TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4362	4366		CHEROKEE
4350	4351		CHEROKEE
4338	4342		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED  
OCT 07 2010

KCC WICHITA

District: 01

Signed Michael J Maier  
(TECHNICIAN)

RECEIVED  
SEP 29 2010  
KCC DODGE CITY

Form CP-23