

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21471-00-00
Spot: E2NE Sec/Twnshp/Rge: 2-21S-23W
1316 feet from N Section Line, 673 feet from E Section Line
Lease Name: WHITLEY Well #: 1-2
County: HODGEMAN Total Vertical Depth: 4472 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		WITH 180 SX CMT
PC		1482		WITH 225 SX CMT
PROD	5.5	4471	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. GEL SPACER TO 1500' THEN CMT TO SURFACE. PUMP 50 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2010 11:15 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT THEN 25 SX GEL & 150 SX CMT. CMT TO SURFACE. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 500#. TIED ONTO BACKSIDE & PUMPED 1/4 BBL. PRESSURE TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4471	4472		MISS OH
4461	4471		MISS
4373	4378		LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

SEP 29 2010

KCC DODGE CITY

Signed

Michael Maier

(TECHNICIAN)

RECEIVED
OCT 07 2010

KCC WICHITA

Form CP 2/4