

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21821-00-00
Spot: NWNESW Sec/Twnshp/Rge: 5-25S-14W
2294 feet from S Section Line, 1648 feet from W Section Line
Lease Name: WILSON Well #: 1
County: STAFFORD Total Vertical Depth: 4410 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3800		
SURF	8.625	346		WITH 250 SX CMT
PROD	4.5	4411	1037	WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/13/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: SET CIBP @ 3800' WITH 2 SX CMT. PULL CASING TO 900' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2010 1:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3800'. 1ST PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3858	3863		LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
OCT 22 2010
KCC WICHITA

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
OCT 15 2010
KCC DODGE CITY

Page 2/3