

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21107-00-00
Spot: NENENW Sec/Twnshp/Rge: 30-16S-16W
342 feet from N Section Line, 2011 feet from W Section Line
Lease Name: URBAN D Well #: 2
County: RUSH Total Vertical Depth: 3600 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3500		
SURF	8.625	1108		WITH 425 SX CMT
PROD	4.5	3599	0	WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2010 9:30 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: RUN TBG TO 3992' & PUMP 6 SX GEL, 50 SX CMR & 200# HULLS. PULL TBG TO 1400' & PUMP UNTIL CMT CIRCULATES AROUND BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2010 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 3392' & PUMP 6 SX GEL & 50 SX CMT WITH 200# HULLS. PULL TBG TO 1400' & PUMPED 110 SX CMT. CIRCULATED CASING. SHUT IN CASING & PUMPED 10 SX CMT. PRESSURED TO 1100#. PULLED TBG & TIED ONTO CASING WITH A SWEDGE. PUMPED 40 SX CMT & PRESSURED TO 1200# & HELD. WENT DOWN BACKSIDE & PUMPED 60 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
3554	3558		
3436	3439		
3417	3421		
3364	3368		
3310	3314		
3297	3301		
3274	3278		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED

NOV 12 2010

KCC DODGE CITY

RECEIVED

NOV 19 2010

KCC WICHITA

Form CP 2/8