

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21136-00-01
Spot: NENWNW Sec/Twnshp/Rge: 30-16S-16W
4946 feet from S Section Line, 4144 feet from E Section Line
Lease Name: URBAN D Well #: 4
County: RUSH Total Vertical Depth: 3801 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1110		WITH 400 SX CMT
PROD	4.5	3783	0	WITH 275 SX CMT

Well Type: EOR UIC Docket No: E23738.1 Date/Time to Plug: 11/03/2010 8:30 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: RUN TBG TO 3400' & PUMP 10 SX GEL, 50 SX CMT & 250# HULLS. PULL TBG TO 1200' & PUMP TILL CMT CIRCULATES AROUND BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2010 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 3445' & PUMP 10 SX GEL & 50 SX CMT WITH 250# HULLS. PULL TBG TO 1200' & PUMPED 115 SX CMT & CIRCULATED CASING. SHUT IN CASING & PUMPED 120 SX CMT. CIRCULATED BACKSIDE. PULLED TBG & TOPPED OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3703	3720		
3430	3434		
3303	3311		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
NOV 19 2010
KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
NOV 12 2010
KCC DODGE CITY

Form CP-27