

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03215-00-00
Spot: NENESESE Sec/Twnshp/Rge: 12-9S-19W
1320 feet from S Section Line, 330 feet from E Section Line
Lease Name: HILGERS Well #: 9
County: ROOKS Total Vertical Depth: 3460 feet

Operator License No.: 34179
Op Name: THOMAS M. BROWN LLC
Address: PO BOX 250
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1401	0	w/500 sxs cmt
PROD	5.5	3456	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JAKE BROWN Company: THOMAS M. BROWN LLC Phone: (785) 737-7070

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 300# hulls.
Perforate at 1390'.
5 1/2" retrievable plug stuck at 3100'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2010 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2900' - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1356'. L-K Wireline perforated 5 1/2" casing at 1390'.
Pumped 60 sxs 60/40 pozmix - 4% gel to circulate cement to surface out 8 5/8"x 5 1/2" annulus.
Closed annulus and pumped 150 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3456	3464		

Remarks: ALLIED CEMENTING COMPANY-TICKET 33950.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN) RECEIVED

CM

DEC 08 2010 Form CP-2/3

KCC WICHITA

DEC 03 2010