

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-15286-00-01  
Spot: N2NE Sec/Twnshp/Rge: 23-11S-19W  
4950 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: DEVINE R P Well #: 2  
County: ELLIS Total Vertical Depth: 3469 feet

Operator License No.: 33699  
Op Name: T-N-T ENGINEERING, INC.  
Address: 9250 E COSTILLA AVE #510  
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3150		
SURF	8.625	1312	0	w/575 sxs
COND	13	128	0	w/200 sxs
PROD	5.5	3464	0	w/200 sxs

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2010 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: RANDY WEIGEL Company: T-N-T ENGINEERING, INC. Phone: (785) 737-3736

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 500# hulls - 8 sxs gel.  
Knocked out CIBP - past 3420'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/22/2010 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech perfed at 1850' and 1276'.  
RIH with tubing to 3250'. Allied rigged to tubing and pumped 8 sxs gel - followed with 80 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.  
Pulled tubing to 1850'. Allied rigged to tubing and mixed and pumped 130 sxs cement with 300# hulls to circulate 5 1/2" casing.  
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 170 sxs cement to circulate cement out 8 5/8" casing.  
Shut in valve - pressured to Max. P.S.I. 1000#. S.I.P. 400#.  
Rigged to 13" casing - instant pressure.

Perfs:

Top	Bot	Thru	Comments
3454	3469		
3244	3250		
3200	3206		

RECEIVED  
NOV 29 2010  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #33999.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

Form CP-2/3

NOV 23 2010