

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22960-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 31-15S-11W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DRISCOLL JOE Well #: 5
County: RUSSELL Total Vertical Depth: 3388 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 9250 E COSTILLA AVE #510
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	582	0	250 SX
PROD	5.5	3385	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2010 8:00 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 525 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2010 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 200' - 575' - 1450'.
Ran tubing to 3070' - pumped 9 sxs gel - followed with 70 sxs cement and 200# hulls.
Pulled to 1480' - pumped 100 sxs cement with 200# hulls.
Pulled to 610' - circulated cement on casing to surface with 100 sxs cement.
Shut in casing - circulated cement to surface on backside with 100 sxs cement.
Pulled tubing - topped off with 15 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2848	3047		

RECEIVED
DEC 06 2010

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

KCC WICHITA

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

DEC 02 2010