

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20255-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 8-11S-16W
3704 feet from S Section Line, 4965 feet from E Section Line
Lease Name: CHESNEY B Well #: 9
County: ELLIS Total Vertical Depth: 3479 feet

Operator License No.: 33996
Op Name: V. FRANCIS WEIGEL FAMILY PARTNE
Address: PO BOX 219
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	164	0	w/135 sxs cmt
PROD	5.5	3478	0	w/190 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2010 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: CECIL WEIGEL Company: V.FRANCIS WEIGEL FAMILY PAR Phone: (785) 637-5383

Proposed Plugging Method: Ordered 535 sxs 60/40 pozmix - 4% gel - 750# hulls - 11 sxs gel.
Pert Tech shot holes at 1600' - 1050' - 500'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2010 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2900'.
Quality rigged to tubing and pumped 11 sxs gel - followed with 75 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1600' - pumped 225 sxs cement with 250# hulls mixed in - no circulation.
Pulled tubing to 800'. Quality rigged to tubing and mixed and pumped 175 sxs cement with 200# hulls mixed in - no circulation.
Pulled tubing to 400'. Quality rigged to tubing and mixed and pumped 50 sxs cement with 100# hulls to circulate cement to surface.
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 5 sxs cement.
Max. P.S.I. 150#. S.I.P. 100#.
Rigged to 8 5/8" casing and pumped 5 sxs cement.
Max. P.S.I. 1000#. S.I.P. 600#.

Perfs:

Top	Bot	Thru	Comments
3319	3324		
3278			
3262	3264		
3255			
3225			
3206	3208		
3184	3188		
3136	3140		
3091	3094		
3080	3084		
3020	3024		

INVOICED

DATE _____


INV. NO. _____

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4138.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

RECEIVED Form CP-2/3

AUG 19 2010

KCC WICHITA

AUG 18 2010

V. FRANCIS WEIGEL

BOX 244

GORHAM, KS. 67640

CONTR SHIELDS DRILLING CO.

GEOL FRANCIS WHISLER

#9 'B' CHESNEY 'OWWO'

8-11-16W
NW SW NW


CTY ELLIS

FIELD LIEB

ELV 1854 KB SPD 3/29/85 CARD ISSUED 7/25/85 IP OIL WELL

API 15-051-20,255-A

LKC 3080-3280 OA
MARM 3318-3322



SMP	Tops	Depth/Datum
ANH	1037+ 817
B/ANH	1074+ 780
TOP	2764- 910
HEEB	2999-1145
TOR	3022-1168
LANS	3046-1192
BKC	3295-1441
ORTD	3431-1577
*MARM	3317-1463
*CONG	3328-1474
*SIMP	3410-1556
*ARB	3437-1583
LTD	3447-1593
DDTD	3479-1625
*NEW LOG TOPS		

OLD INFO: OPERATOR WAS MURFIN DRILLING CO., #1 'B' CHESNEY, SPD 5/13/68, SET 8 5/8 " 164 / 135SX, COMP AS D&A/PENN (CARD ISSUED 5/23/68), CONTR: COMPANY TOOLS

DST (1) 2997-3032 (TOR) / OP 60", REC 15' M, SIP 114-55#, FP 27-36#

DST (2) 3139-65 (LKC) / OP 90", REC 220' MW, W / SCUM OIL, SIP 519-491#, FP 27-109#

NEW INFO: FR 3/18/85, RE-ENTERED 3/29/85, WSH DWN TO OTD, DD 3479 TD, LOGGED, SET 5 1/2 " 3478 / 190SX, SET DV TOOL IN ANH (DEPTH NA), MICT - CO, PF (MARM) 3318-22, AC 3500G, SWB DWN, SO & WTR, PF (LKC) 3278-80, 3262-65 & 3254-56, AC 3000G, SWB DWN, SO & WTR, PF (LKC) 3223-26, 3205-08 & 3184-88, AC 3000G, SWB DWN, SO & WTR, PF (LKC) 3135-39, AC 500G, SWB DWN, SO & WTR, PF (LKC) 3096-3102 & 3080-84, AC 3000G, SWB DWN, SO & WTR, PF (TOR) 3025-28, AC 3000G, SWB BK LD, SWB DWN, NO FIH, SWB DRY, POP (POTENTIAL NOT RPTD), 4/85, COMMINGLED

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS