

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23232-00-00  
Spot: SESENW Sec/Twnshp/Rge: 19-12S-16W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: WEIGEL G Well #: 1  
County: ELLIS Total Vertical Depth: 3660 feet

Operator License No.: 33996  
Op Name: V. FRANCIS WEIGEL FAMILY PARTNE  
Address: PO BOX 219  
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211	0	150 SX
PROD	5.5	3654	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2010 2:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: CECIL WEIGEL Company: V.FRANCIS WEIGEL FAMILY PAR Phone: (785) 637-5383

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 550# hulls - 12 sxs gel.  
Perf Tech perfed at 1650' - 1275' - 650'. PBTD 3602'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2010 6:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 3300'.  
Quality rigged to tubing and mixed and pumped 12 sxs gel - followed with 75 sxs  
60/40 pozmix - 4% gel with 200# hulls mixed in.  
Pulled tubing to 1650'. Quality rigged to tubing and mixed and pumped 210 sxs cement with  
350# hulls mixed in to circulate cement to pit area.  
Pulled tubing and rigged to 5 1/2" casing with a swedge and pumped 25 sxs cement.  
Max. P.S.I. 200#. S.I.P. 200#.  
Rigged to 8 5/8" and pumped 5 sxs cement - blew out between 5 1/2" casing and 8 5/8" casing -  
backside full.

Perfs:

Top	Bot	Thru	Comments
3540			
3496			
3467			
3426	3430		
3415			
3387	3389		
3384	3388		
3363	3366		

INVOICED

DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4139.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

AUG 18 2010

RECEIVED  
AUG 19 2010  
KCC WICHITA

Form CP-2/3

REPLACEMENT CARD

V. FRANCIS WEIGEL

BOX 244  
GORHAM, KS 67640

#1 "G" WEIGEL


19-12-16W  
SE SE NW

CONTR SHIELDS DRILLING CO.

CTY ELLIS

GEOL FRANCIS C. WHISLER

FIELD WEIGEL



ELV 2104 KB SPD 11/9/82

CARD ISSUED 2/24/83

IP P 12 BOPD & WTR  
LKC - INTV NA

LOG	Tops	Depth/Datum	API 15-051-23,232
*ANH	.....	1261+ 843	8 5/8 " 211/150SX, 5 1/2 " 3654/150SX DST (1) 3609-44 (PENN, ARB) / 30-30-30-30, REC 570' SUL- PHUR WTR, SIP 1074-1057#, FP 58-317# MICT - CO, PF (LKC) INTV NA (MULTIPLE ZNS), ACIDIZED (AMT NA), SWB LD, SO, POP, P 12 BOPD & WTR, NO OTHER INFO RE- LEASED BY OPERATOR
*B/ ANH	.....	1300+ 804	
TOP	.....	3042- 938	
HEEB	.....	3285-1181	
TOR	.....	3309-1205	
LKC	.....	3334-1230	
BKC	.....	3569-1465	
ARB	.....	3615-1511	
RTD	.....	3660-1556	
* SAMPLE TOPS			

INFO RELEASED: 10/4/84 - ADDED WELL INFO  
NOTE: CORRECTION: 3/24/83 - ORIGINALLY FIRST REPORTED IN SE SE SE

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS