

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-21984-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 9-30S-3W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: LITTLE Well #: 1  
County: SUMNER Total Vertical Depth: 4320 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 200 W DOUGLAS AVE STE 520  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		200 SX
PROD	4.5	4022	2240	165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2009 12:00 PM  
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3600' AND CAP WITH 4 SKS OF CMT. REC CASING. PULL CASING TO 650' SPOT 35 SKS OF CMT. PULL TO 350' AND CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 09/22/2009 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3600' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2240' AND PULLED TO 650', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 350', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3650	3655	CSG	

Remarks: ALLIED CMTG 60/40 GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
DEC 03 2010  
KCC WICHITA