

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23027-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 15-24S-14W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: NEILL Well #: 3
County: STAFFORD Total Vertical Depth: 4160 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	310		WITH 225 SX CMT
PROD	4.5	4159	2032	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2010 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 11/05/2010 4:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SANDED TO 3975' & 4 SX CMT. 1ST PLUG AT 900' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4056	4060		
4044	4050		
4029	4035		

Remarks: USED 60/40 POZMIX 4% GEL.

Plugged through: CSG

District: 01

Signed

Jerry W. Stapleton
(TECHNICAL)

RECEIVED
DEC - 7 2010
KCC DODGE CITY

RECEIVED
DEC 10 2010
KCC WICHITA

Form CP 2/3