

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20124-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 2-27S-13W
1108 feet from S Section Line, 2246 feet from E Section Line
Lease Name: S AND S UNIT Well #: 1
County: PRATT Total Vertical Depth: 4440 feet

Operator License No.: 33810
Op Name: WALCHER OIL, LC
Address: 150 N MAIN STE 809
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	428		WITH 350 SX CMT
PROD	4.5	4394	0	NA

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/03/2010 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3780' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. BOND LOG 5 1/2" CASING TO FIND CMT TOP. (5 1/2" CASING HAS BEEN SQUEEZED IN.) PERFORATE TOC & FILL 5 1/2" CASING FROM 800' TO SURFACE & FILL 5 1/2" X 8 5/8" ANNULUS FROM TOC TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL
Date/Time Plugging Completed: 11/08/2010 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

11/3/10: WELL BLEW OUT. PUMPED DOWN 2 7/8" TBG WITH 200# HULLS & 30 SX CMT. BOTTOM OF TBG @ 3940'. SHUT WELL IN. 11/4/10: WELL STILL NOT DEAD. CUT TBG OFF @ 2708'. PUMPED DOWN TBG WITH 30 SX COMMON CMT. SHUT WELL IN TO LET CMT SET. WELL DEAD. LAID TBG DOWN. RUN BOND LOG. FOUND CMT FROM 800' TO 380'. 11/5/10: PERFORATED 5 1/2" @ 300'. RUN TBG TO 800'. PACKED OFF HEAD. PUMPED DOWN TBG WITH A TOTAL OF 300 SX CMT. 5 1/2" CASING CIRCULATED CMT AFTER PUMPING 80 SX CMT. SHUT IN TBG/CSG ANNULUS & CONTINUED PUMPING CMT. NEVER ESTABLISHED RETURNS UP 5 1/2"/8 5/8" ANNULUS. HAD SLIGHT BLOW. SHUT DOWN. 11/8/10: TAG TOC IN 5 1/2" CASING @ 500'. RUN TBG IN TO 500' & CIRCULATED CMT TO SURFACE WITH 40 SX CMT. PUMPED DOWN 5 1/2"/8 5/8" ANNULUS WITH 5 SX CMT. PRESSURED TO 1100#.

Perfs:

Top	Bot	Thru	Comments
3970	3974		
3935			
3835	3838		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
NOV 19 2010
KCC DODGE CITY

RECEIVED
DEC 08 2010
KCC WICHITA

Form CP-2/3