

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20780-00-00
Spot: NENWNW Sec/Twnshp/Rge: 30-22S-15W
319 feet from N Section Line, 4297 feet from E Section Line
Lease Name: GILCREASE Well #: 1
County: PAWNEE Total Vertical Depth: 4082 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S WEBB RD STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3850		
SURF	8.625	403		WITH 250 SX CMT
PROD	4.5	4024	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/10/2010 9:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: LUKE DYKES Company: YOUNGER ENERGY Phone: (316) 681-2542

Proposed Plugging Method: THERE ARE 84 JTS. 2 3/8" TUBING STUCK IN HOLE @ 900'. PLAN TO CEMENT TUBING IN PLACE. PUMP 50 SXS DOWN TUBING, DISPLACE WITH 25 BBLS. WATER. CEMENT PLUG SHOULD BE AT APPROXIMATELY 3500'. SHOOT OFF TUBING IN ANHYDRITE, APPROXIMATELY @ 960'. PERFORATE PRODUCTION CASING AT APPROXIMATELY 960'. PUMP 100 SXS TO SURFACE. TOP OFF AND SQUEEZE THE BACK SIDE AT THE SURFACE AS REQUIRED.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2010 5:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CASING SQUEEZED @ 554-584' WITH 250 SX CMT. 2604' OF TBG STUCK IN HOLE. TOP OF FISH @ 488'. BOTTOM OF FISH @ 2604'. 1ST PLUG PUMPED 50 SX CMT THROUGH TBG @ 2604'. DISPLACE WITH 25 BBLS WATER. EST. TOC @ 3500'. 2ND PLUG ATTEMPT TO SHOOT-OFF TBG @ 840' & 805'. TRIED TO CIRCULATE WATER. SHOT TBG @ 790'. PRESSURE TO 1600#. MIXED & PUMPED 50 SX CMT AT 790'. 3RD PLUG SHOT TBG @ 488'. MIXED & PUMPED 100 SX CMT. CMT CAME TO WITHIN 30' OF SURFACE. 4TH PLUG PUMP 7 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. SHUT IN PRESSURE 500#. 5TH PLUG TOP OFF CASING WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3952	3956		
3906	3912		
3896	3900		
3882	3888		
3576	3582		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
NOV 19 2010
KCC DODGE CITY

RECEIVED
NOV 24 2010
KCC WICHITA