

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05296-00-00
Spot: SENENE Sec/Twnshp/Rge: 35-15S-13W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: SELLENS Well #: 5
County: RUSSELL Total Vertical Depth: 3346 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3275		
SURF	8.625	520	0	275 SX
PROD	5.5	3338	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CHARLES SCHMIDT Company: ZENITH DRILLING CORPORATION Phone: (316) 755-3523

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1600' - 885' - 450'.
Ran tubing to 3205'. Tied to tubing and pumped 10 sxs gel - followed with 580 sxs cement with 200# hulls.
Pulled tubing to 1600' - pumped 100 sxs cement with 300# hulls.
Pulled to 500' - circulated to surface with 45 sxs cement - pulled all tubing.
Topped off with 5 sxs cement.
Tied to backside - pressured up to 300# P.S.I. - had been squeezed.

Perfs:

Top	Bot	Thru	Comments
3142	3150		
3096	3100		
3074	3080		
2949	3000		
2939	2943		

RECEIVED
DEC 03 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANU.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM