

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-13092-00-01
Spot: S2NWNE Sec/Twnshp/Rge: 20-21S-12W
4290 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SYMS FLORENCE Well #: 1
County: STAFFORD Total Vertical Depth: 3594 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 17 ARENTZEN BLVD, STE 203
CHARLEROL, PA 15022

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	245		WITH 185 SX CMT
PROD	5.5	3591	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2011 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: DALTON POPP Company: EMPIRE ENERGY Phone: (620) 786-5514

Proposed Plugging Method: RUN TBG BETWEEN ARBUCKLE & KANSAS CITY PERFS. PUMP 10 SX GEL - 50 SX CMT. PULL TBG TO 700' & CIRCULATE 5 1/2" CASING FULL TO SURFACE. CHECK 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2011 10:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

8 5/8" X 5 1/2" ANNULUS CEMENTED FROM 1100' TO 0'. 4/18/11: COMPANY DUG OUT THE WELLHEAD & VISUALLY FOUND CMT AT SURFACE BETWEEN 8 5/8" X 5 1/2". RAN TBG TO 3538' & PUMPED 10 SX GEL FOLLOWED BY 50 SX CMT. PULLED TBG TO 700'. CIRCULATED CMT TO SURFACE WITH 80 SX CMT. PULLED TBG OUT & TOPPED OFF 5 1/2" WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3591	3594		
3430	3434		OHIO
3376	3384		OHIO

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

RECEIVED

APR 25 2011

KCC WICHITA

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

APR 22 2011

KCC DODGE CITY

Form CR-20