

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22606-00-00  
Spot: N2NESES Sec/Twnshp/Rge: 15-33S-39W  
1200 feet from S Section Line, 2319 feet from W Section Line  
Lease Name: PHYLLIS Well #: 15 #1  
County: STEVENS Total Vertical Depth: 6600 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6345		WITH 5 SX CMT
SURF	8.625	1668		WITH 500 SX CMT
PROD -4.5		6593	3219	WITH 235 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/14/2011 8:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 6345' WITH 2 SX CMT. CUT 4 1/2" CASING & POOH WITH CASING. RIH WITH TBG TO 1700' & SPOT 120 SX CMT. PLUG AT 590' WITH 60 SX CMT. PLUG AT 60' TO SURFACE.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/18/2011 12:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 6345' WITH 5 SX CMT. CUT 4 1/2" CASING AT 3219' & POOH WITH CASING. 1ST PLUG RIH WITH TBG & SPOTTED 120 SX CMT AT 1700'. 2ND PLUG AT 590' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6395	6401		ST. LOUIS

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED

APR 25 2011

KCC WICHITA

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED

APR 19 2011

KCC DODGE CITY

Form CP-33