

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03940-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 24-17S-11W
4950 feet from S Section Line, 1980 feet from E Section Line
Lease Name: PETERMAN Well #: 2
County: BARTON Total Vertical Depth: 3282 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	285	0	125 SX
PROD	5.5	3265	0	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2011 4:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING, INC. Phone: (620) 792-7607

Proposed Plugging Method: Ordered 240 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2011 8:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1380' - 615' - 250'.
Ran tubing to 3000' - tied to tubing - pumped 13 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1416' - tied to tubing - pumped 180 sxs cement - circulated cement to surface on casing.
Pulled tubing - tied to casing - pumped 60 sxs cement - circulated backside to surface.
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3016	3216		LKC

RECEIVED

Remarks: QUALITY WELL SERVICE.

Plugged through: CSG

APR 25 2011

KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

APR 21 2011