

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03942-00-00  
Spot: S2SWNE Sec/Twnshp/Rge: 24-17S-11W  
2970 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: PETERMAN Well #: 4  
County: BARTON Total Vertical Depth: 3322 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	304	0	140 SX
PROD	5.5	3285	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/14/2011 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING, INC. Phone: (620) 792-7607

Proposed Plugging Method: Ordered 240 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/14/2011 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1380' - 615' - 250'.  
Ran tubing to 3150' - tied to tubing - pumped 13 sxs gel - followed with 50 sxs cement and 200# hulls.  
Pulled tubing to 1400' - tied to tubing - pumped 235 sxs cement - circulated cement to surface on casing.  
Pulled tubing - tied to casing - pumped 55 sxs cement - circulated backside to surface.  
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3044	3236		LKC

RECEIVED  
APR 25 2011

Remarks: QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

APR 21 2011