

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-01178-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 36-30S-2W
2970 feet from S Section Line, 330 feet from W Section Line
Lease Name: RINER Well #: 2
County: SUMNER Total Vertical Depth: 3840 feet

Operator License No.: 31822
Op Name: JOLEN OPERATING COMPANY
Address: 100 N BROADWAY AVE STE 2460
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	454		300 SX
PROD	5.5	3839		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2010 8:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: PERRY S. HENMAN Company: JOLEN OPERATING CO Phone: (785) 623-8525

Proposed Plugging Method: PER KCC RECOMMENDATIONS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 11/03/2010 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

RAN TUBING TO 3757' & SPOTTED 35 SKS COMMON 3% CACL 2% GEL. PULL TUBING TO 2017' & SPOTTED 35 SKS COMMON 3% CACL 2% GEL. PERFORATED CASING AT 504'-505'. RAN TUBING TO 516' ON STRIPPING HEAD. CIRCULATED WATER UP BACKSIDE OF 5 1/2 CASING. PUMPED 195 SKS CMT DOWN TUBING AND CIRCULATED UP 5 1/2 CASING. CLOSED CASING VALVE & CIRCULATED CMT UP THE 5 1/2 - 8 5/8 ANNULAS.

Perfs:

Top	Bot	Thru	Comments
3768	3778		MISSISSIPPI

RECEIVED
11-9-10
NOV 09 2010


Remarks: CONSOLIDATED CMT #29936

Plugged through: TBG

KCC WICHITA

District: 02

Signed _____



(TECHNICIAN)