

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23912-00-00

Spot: NWSWSE

Sec/Twnshp/Rge: 9-7S-17W

990 feet from S Section Line, 2306 feet from E Section Line

Lease Name: MCREYNOLDS TRUST

Well #: 9-1

County: ROOKS

Total Vertical Depth: 3486 feet

Operator License No.: 34351

Op Name: MARALEX RESOURCES, INC.

Address: 775 GODDARD AVE PO BOX 338  
IGNACIO, CO 81137

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	473		

Well Type: DH

UIC Docket No:

Date/Time to Plug: 11/29/2010 10:00 AM

Plug Co. License No.: 33493

Plug Co. Name: AMERICAN EAGLE DRILLING LLC

Proposal Rcvd. from: PETE WAGNER

Company: MARALEX RESOURCES, INC.

Phone: (970) 563-4000

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS

WitnessType: NONE

Date/Time Plugging Completed: 11/30/2010 2:30 AM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st. Plug at 3415' w/25 sxs.  
2nd. Plug at 1325' w/25 sxs.  
3rd. Plug at 775' w/100 sxs.  
4th. Plug at 500' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
DEC 03 2010  
KCC WICHITA

District: 04

Signed

*Case Morris*

(TECHNICIAN)

Form CP-2/3

DEC 01 2010