

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20738-00-00  
Spot: SESENWNW Sec/Twnshp/Rge: 13-23S-34W  
4030 feet from S Section Line, 4030 feet from E Section Line  
Lease Name: BIDWELL Well #: 2-13  
County: FINNEY Total Vertical Depth: 4605 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL RD STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2698		WITH 5 SX CMT
SURF	8.625	926		WITH 400 SX CMT
PROD	5.5	3160	1002	WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/23/2010 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: SAUL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: FILL 5 1/2" WITH 400# HULLS & CMT TO 0'. FILL ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/24/2010 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 2698' WITH 5 SX CMT. 2ND PLUG RIHWT TO 2000' PUMP 25 SX CMT. 3RD PLUG RUN BOND LOG: TOC @ 1310'. SHOT OFF CASING @ 1002'. TOO H W/ 1/2" CASING. RIHWT TO 1023'. PUMP 50 SX CMT. 4TH PLUG PULL OUT OF HOLE TO 434' & PUMP 50 SX CMT. 5TH PLUG POOH TO 64' & PUMP 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2748	2855		

RECEIVED  
OCT 22 2010

Remarks: USED CLASS CM CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

KCC WICHITA

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED

OCT 13 2010

KCC DODGE CITY

Form B-2/3