

00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20065-00-01
Spot: SWSESESE Sec/Twnshp/Rge: 7-22S-3W
280 feet from S Section Line, 615 feet from E Section Line
Lease Name: CLARENCE FROESE Well #: 3
County: HARVEY Total Vertical Depth: 3775 feet

Operator License No.: 3942
Op Name: MONROE, ORVILLE DBA BIG "O"
Address: 2820 PASEO DR
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	545		100 SX
COND	13	275		250 SX
PKR	7	3500		
PKR		3658		
PROD	7	3675		100 SX

Well Type: SWD UIC Docket No: D14505.0 Date/Time to Plug: 11/30/2010 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2010 11:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

KELSO RAN TUBING TO 3450'. TRIED GETTING SOMETHING BETWEEN THE 13" & 10 3/4". KELSO CUT OFF THE UPSET ON A PIECE OF 1" AND THEN SMASHED IT FLAT. THEY GOT IT ABOUT 9' DOWN TRIED FILLING VOID FULL OF WATER GOT LESS THAN 10 SX IN IT. THEY THEN SWITCHED TO THE 2" AND PUMPED A BOTTOM PLUG @ 3450' USED 6 SX HULLS & 50 SX COMMON WITH 2% CACL. KELSO'S THEN PULLED 20 JOINTS AND WAIT ONE HOUR TO GO IN AND TAG PLUG. KELSO'S TAGGED BOTTOM PLUG @ 3200'. THEY THEN PULLED TUBING UP TO 600'. COPELAND TIED ON AND STARTED PUMPING CEMENT. THEY CIRCULATED CEMENT TUBING FROM 600' TO SURFACE INSIDE THE 7". THEY THEN PULLED THE TUBING AND TIED ON TO THE 7". THEY STARTED BULL HEADING CEMENT DOWN THE 7" AND GOT GOOD CIRCULATION ON THE BACKSIDE @ 100 PSI. AT 160 SX LOST PRESSURE AND CONTINUED PUMPING TILL LOST CIRCULATION. THEY BROKE OFF THE 7" AND FOUND IT TO BE ON A VACUUM. WILL COME BACK AND TAG IN THE MORNING AND GO FROM THERE. (5-10 SX BETWEEN 13" & 10.75", 140 SXS TO CIRCULATE FROM 600' TO SURFACE OF 7", 285 SX BULL HEADED DOWN CASING. TOTAL CEMENT 50 SX COMMON & 430 SX 60/40 POS W/4% GEL TK # 37402. 12/1/2010 KELSO RAN IN AND TAGGED CEMENT INSIDE 7" @ 430'. THEY TAGGED ON THE BACKSIDE @ 290'. COPELAND OUT AND PUMPED 75 SXS DOWN THE BACKSIDE TO CIRCULATE TO SURFACE, AND PUMPED 70 SX DOWN THE 7" TO CIRCULATE TO SURFACE (145 SX 60/40 POS W/4% GEL TK #C37402)

Perfs:

Top	Bot	Thru	Comments
3667	3677	OH	
3352	3368	CSG	

Remarks: PACKERS LEFT IN HOLE @ 3500' & 3658'

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

RECEIVED

DEC 10 2010

Form CP-2/3

KCC WICHITA

1/2