

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19126-00-00
Spot: SESWNW Sec/Twnshp/Rge: 15-19S-4E
3059 feet from S Section Line, 4282 feet from E Section Line
Lease Name: THIES A Well #: 4
County: MARION Total Vertical Depth: 2277 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2277		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2010 10:00 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: DAN WEINHOLD Company: _____ Phone: (785) 483-1599

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2010 5:15 PM KCC Agent: SHANE JONES

Actual Plugging Report:

Perfs:

OPERATOR HAS TUBING AND RODS STUCK IN THE HOLE. THEY HAVE TRIED FOR THE LAST 3 TO 4 WEEKS TO FISH RODS AND TUBING OUT. OPERATOR HAS GOT DOWN TO 75' TO TOP OF TUBING AND RODS. OPERATOR HAS NEVER GOT THE WELL TO CIRCULATE TO SURFACE. FLUID IS APPROX 12' DOWN FROM SURFACE. THE LAST THING OPERATOR DID WAS RUN A TAR BLOCK. IT SHOWED HALF MOON OF 4.5" CASING. APPEARS CASING IS PARTED @ 70'. J KLOCK (DIST 2 SUPERVISOR GAVE PERMISSION TO RUN TUBING TO 75' AND CIRCULATE CEMENT. 11/30/2010 OPERATOR IS GOING TO MUD UP AND SEE IF THEY CAN GET CIRCULATION. THEY MIXED 100 BBLs OF HEAVY MUD AND HULLS. THEY PUMPED THE FIRST 100 BBLs IN AND ONLY GOT A LITTLE SHOW OF CIRCULATION. THEY MIXED UP ANOTHER 80 BBLs OF MUD AND HULLS. THEY STARTED PUMPING IT DOWN THE HOLE AND GOT CIRCULATION AT ABOUT 20 BBLs IN TO IT. AS SOON AS THEY STOPPED PUMPING MUD WOULD START FALLING BACK. THEY KEEP WORKING MUD IN A COUPLE OF BARRELS AT A TIME. AT 4:30 PM IT WAS DECIDED TO RUN TUBING TO 75' AND TRY AND CIRCULATE CEMENT. QUALITY CEMENTING TIED ON AND PUMPED 45 SXS GOT GOOD CIRCULATION UP THE BACKSIDE AND INSIDE THE 4.5". THEY PULLED TUBING AND CEMENT STARTING TO FALL BACK. WILL COME OUT TOMORROW AND TAG CEMENT. USED 45 SX 60/40 POS W/4% GEL & 4% CAC1. TK #4484. 12/1/2010 THEY RAN IN AND TAGGED CEMENT @ 12'. THEY WILL CUT OFF CASING @ 3' BELOW GROUND LEVEL AND DRY SACK IT TO SURFACE.

Remarks:

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

DEC 10 2010 Form CP-2/3

KCC WICHITA