

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25441-00-00
Spot: N2NWSWSE Sec/Twnshp/Rge: 29-16S-13W
1040 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HARRINGTON Well #: 11
County: BARTON Total Vertical Depth: 3475 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: 125 N MARKET STE 1230
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	389	0	225 sx
PROD	5.5	3460	2462	150sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2010 12:00 PM
Plug Co. License No.: 31714 Plug Co. Name: NOVY OIL & GAS, INC.
Proposal Rcvd. from: KIRK GLENN Company: NOVY OIL & GAS, INC. Phone: (620) 282-2212

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 2462'.
Pulled casing to 1600' - pumped 125 sxs cement with 300# hulls.
Pulled to 875' - pumped 40 sxs cement with 100# hulls.
Pulled to 500' - pumped 40 sxs cement with 100# hulls.
Pulled to 200' - pumped 60 sxs cement - circulated to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3378	3384		
3374	3378		
3336	3340		
3233	3236		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

RECEIVED

DEC 06 2010

KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

DEC 02 2010