

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22622-00-00  
Spot: NESWNWNW Sec/Twnshp/Rge: 2-14S-21W  
940 feet from N Section Line, 620 feet from W Section Line  
Lease Name: BERNADINE Well #: 1-2  
County: TREGO Total Vertical Depth: 4046 feet

Operator License No.: 31120  
Op Name: PELICAN HILL OIL & GAS, INC.  
Address: 1401 N EL CAMINO REAL SUITE 207  
SAN CLEMENTE, CA 92672

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	342		200 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2009 9:30 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: \_\_\_\_\_ Company: PELICAN HILL OIL & GAS, INC. Phone: (949) 498-2101

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 09/11/2009 10:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 1690' w/25 sxs.  
2nd. Plug at 845' w/100 sxs.  
3rd. Plug at 400' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed *R. Williams*  
(TECHNICIAN)

CM

RECEIVED  
NOV 22 2010  
KCC WICHITA

Form CP-2/3

NOV 17 2010