

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20433-00-00  
Spot: W2NENENE Sec/Twnshp/Rge: 34-11S-33W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SIEMERS Well #: 1  
County: LOGAN Total Vertical Depth: 4680 feet

Operator License No.: 8541  
Op Name: PETEX, INC.  
Address: 4175 S FR 193  
ROGERSVILLE, MO 65742

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 212        | 0           | 145 SX   |
| PROD   | 4.5   | 4677       | 0           | 180 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2010 12:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LARRY CHILDRESS Company: PETEX, INC. Phone: (417) 887-1225

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/24/2010 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 212' w/145 sxs cement.  
4 1/2" production casing set at 4677' w/180 sxs cement.  
DV Tool at 1701' w/400 sxs. TD 4680'. PBTD 4676'.  
Perforated 4 1/2" production casing at 2595'.  
Connected to 4 1/2" production casing - pumped 325 sxs cement mixed with 450# hulls.  
Connected to 8 5/8" surface casing - pumped 20 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4588 | 4594 |      |          |

Remarks: ALLIED CEMENTING COMPANY-TICKET #35515.

Plugged through: CSG

RECEIVED  
DEC 06 2010  
KCC WICHITA

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Form CP-2/3

NOV 24 2010