

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20462-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 18-11S-32W
2310 feet from S Section Line, 3960 feet from E Section Line
Lease Name: ZERR Well #: 1
County: LOGAN Total Vertical Depth: 4690 feet

Operator License No.: 8541
Op Name: PETEX, INC.
Address: 4175 S FR 193
ROGERSVILLE, MO 65742

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 219 | 0 | 140 SX |
| PROD | 4.5 | 4378 | 0 | 175 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2010 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LARRY CHILDRESS Company: PETEX, INC. Phone: (417) 887-1225

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 350# hulls.
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/24/2010 10:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 219' w/140 sxs.
4 1/2" production casing set at 4378' w/175 sxs.
DV Tool at 2586' w/393 sxs. TD 4690'. PBTD 4377'.
Connected to 4 1/2" production casing - pumped 325 sxs cement mixed with 200# hulls.
Connected to 8 5/8" surface casing - pumped 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4266 | 4269 | | |
| 4152 | 4154 | | |
| 4143 | 4146 | | |

Remarks: ALLIED CEMENTING COMPANY-TICKET #35514.

Plugged through: CSG

RECEIVED

DEC 06 2010

KCC WICHITA

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

NOV 24 2010