

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22537-00-00
Spot: SESWNESE Sec/Twnshp/Rge: 30-15S-21W
1536 feet from S Section Line, 975 feet from E Section Line
Lease Name: DOUBLE F RANCH Well #: 1-30
County: TREGO Total Vertical Depth: 4309 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215	0	160 SX
T1	2.375	4289		
PROD	5.5	4309	0	185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2010 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: PINTAIL PETROLEUM, LTD. Phone: (785) 798-3641

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 200# hulls - 15 sxs gel.
Port collar at 1656' - circulate with cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2010 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4290' - pumped 15 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 2350' - pumped 130 sxs cement.
Pulled tubing to 1200' - pumped 100 sxs cement - good circulation of cement.
Pulled tubing out - topped off with 10 sxs cement.
Tied onto backside and pumped 10 sxs cement.
Max. P.S.I. 200#. Shut in.

Perfs:

Top	Bot	Thru	Comments
4210	4214		CHEROKEE SAND
4191	4194		CHEROKEE SAND

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

RECEIVED

DEC 08 2010 form CP-2/3

KCC WICHITA

DEC 06 2010