

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21278-00-00
Spot: NWNESE Sec/Twnshp/Rge: 32-25S-16W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: ENGLISH A Well #: 1
County: EDWARDS Total Vertical Depth: 4510 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4010		WITH 2 SX CMT
CIBP		4350		WITH 2 SX CMT
SURF	8.625	337		WITH 180 SX CMT
PROD	4.5	4507	1310	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2010 1:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 770-0955

Proposed Plugging Method: CIBP @ 4000' & 2 SX CMT. CIBP @ 4360' & 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 11/08/2010 8:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4350' WITH 2 SX CMT. SET CIBP @ 4010' WITH 2 SX CMT. 1ST PLUG AT 1062' WITH 15 SX GEL & 50 SX CMT. MUCH DIFFICULTY PULLING PIPE. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4474	4480		
4412	4415		
4065	4069		

RECEIVED
NOV 19 2010

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

KCC WICHITA

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED

NOV 15 2010

KCC DODGE CITY

Form CP 2/3