

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20324-00-00
Spot: E2W2W2NW Sec/Twnshp/Rge: 22-27S-29W
1321 feet from N Section Line, 332 feet from W Section Line
Lease Name: JW Well #: 1-22
County: GRAY Total Vertical Depth: 6196 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 1601 NW EXPRESSWAY, STE 1300
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5850		
SURF	8.625	1684		WITH 550 SX CMT
COND	20	135		WITH 15 YDS GROUT
PROD	4.5	6186	2822	WITH 345 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/03/2010 12:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 100# HULLS & 20 SX CMT. PLUG AT 1710' WITH 50 SX CMT. PLUG AT 900' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2010 3:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PUMP 100# HULLS & 20 SX CMT. DISPLACE TO 5000'. 1ST PLUG LOAD HOLE WITH MUD & PUMP 50 SX CMT AT 1710'. 2ND PLUG AT 900' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5888	5893		
5069	5073		

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Jerry W. Stapleton
(TECHNICIAN)

RECEIVED
DEC - 6 2010
KCC DODGE CITY

RECEIVED
DEC 10 2010
KCC WICHITA