

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21599-00-00
Spot: E2W2NE Sec/Twnshp/Rge: 21-30S-18W
3899 feet from S Section Line, 1726 feet from E Section Line
Lease Name: COBB Well #: 1-21
County: KIOWA Total Vertical Depth: 5530 feet

Operator License No.: 32781
Op Name: ROBERTS RESOURCES, INC.
Address: 2020 N TYLER RD, STE 106
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5000		WITH 2 SX CMT
SURF	8.625	618		WITH 300 SX CMT
PROD	5.5	5230	2040	WITH 150 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/16/2010 1:00 PM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: KENT ROBERTS Company: ROBERTS RESOURCES Phone: (316) 721-2817

Proposed Plugging Method: SET CIBP @ 5000' W/ 2 SX CEMENT. SHOOT CASING APPROXIMATELY 2500', PULL CASING TO 1175' DISPLACE 15 SX GEL & 50 SX CEMENT. PULL CASING TO 640' DISPLACE 50 SX. PULL CASING TO 40' AND CIRCULATE CEMENT TO SURFACE W/ 20 SX. ALL CEMENT IS 60/40 POZ 4% GEL.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2010 4:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 1190' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 640' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5026	5036		W/ 4SPF

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Jerry W. Stapleton
ORRITT (TECHNICIAN)

RECEIVED
NOV 22 2010
KCC DODGE CITY

RECEIVED
NOV 24 2010
KCC WICHITA