

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21472-00-00
Spot: N2SENE Sec/Twnshp/Rge: 9-29S-18W
1664 feet from N Section Line, 654 feet from E Section Line
Lease Name: MCKINLEY Well #: 1
County: KIOWA Total Vertical Depth: 5065 feet

Operator License No.: 32781
Op Name: ROBERTS RESOURCES, INC.
Address: 2020 N TYLER RD, STE 106
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4750		WITH 2 SX CMT
SURF	8.625	472		WITH 305 SX CMT
PROD	5.5	5055	2522	WITH 190 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/09/2010 1:00 PM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: KENT ROBERTS Company: ROBERTS RESOURCES Phone: (316) 721-2817

Proposed Plugging Method: SET CIBP @ 4750' W/ 2 SX CEMENT. SHOT CASING APPROXIMATELY 2500', PULL CASING TO 1260' DISPLACE 15 SX GEL & 50 SX CEMENT. PULL CASING TO 500' DISPLACE 50 SX. PULL CASING TO 40' AND CIRCULATE CEMENT TO SURFACE W/ 20 SX. ALL CEMENT IS 60/40 POZ 4% GEL.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2010 12:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

11/09/2010: SET CIBP @ 4750' WITH 2 SX CMT. 1ST PLUG AT 1265' WITH 15 SX GEL & 50 SX CMT. 11/10/2010: 2ND PLUG AT 511' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4947	4951		
4852	4858		
4807	4812		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

Jerry W Stapleton
PARTIAL (TECHNICIAN)

RECEIVED

NOV 19 2010

KCC DODGE CITY

RECEIVED
NOV 23 2010
KCC WICHITA

Form CS-273