

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-00079-00-02
Spot: NESWNW Sec/Twnshp/Rge: 36-26S-5E
3835 feet from S Section Line, 4379 feet from E Section Line
Lease Name: PETERSON Well #: 3 A
County: BUTLER Total Vertical Depth: 2785 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 333 N PORTLAND AVE
OKLAHOMA CITY, OK 73107

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2250		
SURF	8.625	100		100 SX
PROD	4.5	2784		100 SX

Well Type: SWD UIC Docket No: D26294.0 Date/Time to Plug: 07/14/2010 8:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY Phone: (316) 321-0550

Proposed Plugging Method: COLLAPSED 4-1/2" CASING @ 1800', 35 SXS @ 1800' OR 100' COVER, CIRC, CIRC. 250'-0', USE CLASS A COMMON W/CC SO WE CAN TAG PLUG

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/14/2010 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1752', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & PUMPED 35 SXS CLASS A 3% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 1633', RIH W/RUBBER PLUG & TBG @ 254', CONSOLIDATED ESTABLISHED CIRCULATION & PUMPED 115 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:00 P.M., 7-14-2010. CONSOLIDATED CEMENT TICKET #28487.

Perfs:

Top	Bot	Thru	Comments
2180	2200	CSG	

RECEIVED
NOV 02 2010
KCC WICHITA
INVOICED

DATE _____
INV. NO. _____

Remarks: CEMENT TO SURFACE ON BACKSIDE OF 4-1/2" CASING, PERFS @ 240' SQUEEZED 4-1/2" CASING W/151 SXS CEMENT.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)