

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22791-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 16-13S-17W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: FRANK SCHMIDT Well #: 1
County: ELLIS Total Vertical Depth: 3606 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240	0	150 SX
PROD	5.5	3605	0	550 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2010 9:30 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN WEAVERLY Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls - 16 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2010 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Western Well Service RIH with tubing to 3500'.
Quality Oil Well rigged to tubing and mixed and pumped 14 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1650'.
Quality Oil Well rigged to tubing and mixed and pumped 155 sxs cement with 200# hulls to circulate cement to surface.
Pulled tubing. Topped off 5 1/2" casing with 10 sxs cement. Hole standing full.
Dug out 8 5/8" head - rigged to head. Had instant pressure to 600#.

Perfs:

Top	Bot	Thru	Comments
3556	3560		

INVOICED
DATE _____
INV. NO. _____

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4465.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

RECEIVED
DEC 08 2010

Form CP-2/3

DEC 06 2010

KCC WICHITA