

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-19085-00-01
Spot: NENENWNE Sec/Twnshp/Rge: 15-21S-14W
4957 feet from S Section Line, 1601 feet from E Section Line
Lease Name: ANSHUTZ Well #: 2
County: STAFFORD Total Vertical Depth: 3945 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	339		WITH 240 SX CMT
L1	4.5	3306		WITH 125 SX CMT
PROD	5.5	3878	0	WITH 125 SX CMT

Well Type: SWD UIC Docket No: D17893.0 Date/Time to Plug: 11/03/2010 10:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: GEORGE STOPPELWORTH Company: JOHN JAY DARRAH, JR. Phone: (316) 219-3390

Proposed Plugging Method: TAG BOOTM & PUMP 50 SX CMT W/HULLS. PULL TBG TO 900' & CIRCULATE CMT. CHECK 8 5/8" X 5 1/2" ANNULUS WITH CMT. CHECK 5 1/2" X 4 1/2" ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2010 11:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

5 1/2" IS SQUEEZED FROM 880' TO 0'. RAN TBG TO 3364' & TAGGED BOTTOM. PULLED TBG TO 3344' & PUMPED 50 SX CMT WITH 150# HULLS. PULLED TBG TO 887' & CIRCULATED CMT TO SURFACE UP 4 1/2" WITH 115 SX CMT. PULLED TBG OUT OF HOLE. TOPPED OFF 4 1/2" WITH 10 SX CMT. PRESSURED 5 1/2" X 4 1/2" ANNULUS TO 500 PSIG WITH 5 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 800 PSIG WITH 1 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3501	3506		LKC "H"

INVOICED
DATE _____
IN. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

NOV 15 2010

KCC WICHITA

RECEIVED

NOV - 9 2010

KCC DODGE CITY

Form CP 2/3