

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21054-00-00
Spot: NENWSE Sec/Twnshp/Rge: 9-12S-21W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MUSGRAVE Well #: 9-10
County: TREGO Total Vertical Depth: 4120 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	296	0	200 SX
PROD	4.5	4119	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2010 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GEORGE STOPPLEWORTH Company: DARRAH, JOHN JAY, JR. Phone: (316) 263-2243

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls - 8 sxs gel.
Alt II at 1800' w/500 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2010 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3970' - pumped 8 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1800' - pumped 100 sxs cement - good circulation of cement.
Pulled tubing out - filled casing with 30 sxs cement.
Checked backside - had cement to surface.

Perfs:

Top	Bot	Thru	Comments
4014	4019		ARBUCKLE
3999	4001		ARBUCKLE
3966	3972		MARMATON

INVOICED

DATE _____
INV. NO. _____

Remarks: SWIFT CEMENTING COMPANY-TICKET #19327.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

NOV 17 2010

NOV 12 2010

KCC WICHITA