

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20664-00-00

Spot: NWNE

Sec/Twnshp/Rge: 14-21S-43W

3821 feet from S Section Line, 1450 feet from E Section Line

Lease Name: BARRETT

Well #: 1B-14

County: HAMILTON

Total Vertical Depth: 5250 feet

Operator License No.: 33017

Op Name: DAVIS OPERATING COMPANY

Address: 2800 MID CONTINENT TOWER
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	13.38	1401		WITH 1150 SX CMT
PROD	8.625	2400		WITH 500 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 08/02/2010 2:00 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/05/2010 4:00 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

PBTD @ 2310' WITH CMT PLUG # OF SACKS UNAVAILABLE. 1ST PLUG PACKER SET @ 2256'-PUMPED 30 SX CMT THROUGH TBG- DISPLACED WITH WATER. MAXIMUM SQUEEZE PRESSURE WAS 1500#. WAIT ON CMT 18 HOURS & TAG TOC @ 2118'. TESTED CASING BELOW PACKER TO 500#. 2ND PLUG PULL TBG & PACKER, ATTEMPTED TO PULL 8 5/8". NO STRETCH. RIHWT TO 1430' & PUMP 40 SX CMT. 3RD PLUG PULL TBG TO 1000' & PUMP 50 SX CMT. 4TH PLUG PULL TBG TO 50' & PUMP 15 SX CMT. 5TH PLUG RAN 1" TBG BETWEEN 13 3/8" X 8 5/8" ANNULUS. STACKED OUT AT 15'. PUMPED 7 SX CMT TO FILL ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2254	2256		
2231	2232		
2223	2225		
2200	2204		
2187	2190		

INVOICED

DATE _____

INV. NO. _____

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

AUG 17 2010

KCC DODGE CITY

RECEIVED

AUG 30 2010

KCC WICHITA

Form CP-207