

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20662-00-01  
Spot: SWSW Sec/Twnshp/Rge: 18-33S-19W  
812 feet from S Section Line, 4414 feet from E Section Line  
Lease Name: BAKER Well #: 1-18  
County: COMANCHE Total Vertical Depth: 6490 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W 93 N PO BOX 360  
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5155		WITH 2 SX CMT
SURF	8.625	607		WITH 225 SX CMT
PROD	4.5	5455	3006	WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2010 9:30 AM  
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC  
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM Phone: (620) 792-6710

Proposed Plugging Method: SET CIBP @ 5185' WITH 2 SX CMT. PLUG AT 990' WITH 12 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 270' WITH 30 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/24/2010 1:55 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5155' WITH 2 SX CMT. 1ST PLUG AT 1043' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5250	5257		MISSISSIPPI
5236	5240		MISSISSIPPI

**INVOICED**

DATE \_\_\_\_\_

INV. NO. \_\_\_\_\_

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
NOV 30 2010  
KCC DODGE CITY

RECEIVED  
DEC 08 2010

KCC WICHITA

Form CD 2/3