

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-01002-00-01
Spot: SENW Sec/Twnshp/Rge: 24-25S-35W
3344 feet from S Section Line, 3302 feet from E Section Line
Lease Name: BANKETTE Well #: 3 OWWO
County: KEARNY Total Vertical Depth: 5261 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4775		WITH 2 SX CMT
CIBP		4880		
CIBP		5000		
SURF	8.625	1873		WITH 725 SX CMT
PROD	5.5	5175	1973	WITH 255 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2010 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RIGO Company: H2 PLAINS WELL SERVICE Phone: (620) 792-6702

Proposed Plugging Method: CIBP @ 4775' OR 100# HULLS & 25 SX CMT. PLUG AT 1910' WITH 15 SX GEL & 60 SX CMT. PLUG AT 830' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2010 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4775' WITH 2 SX CMT. 1ST PLUG AT 1988' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 835' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5098	5100		ST LOUIS C
4950	4953		LOWER MORROW
4821	4824	OH	UPPER MORROW

INVOICED

DATE _____
INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

NOV 24 2010

KCC DODGE CITY

Signed _____

Ken Jehlik

(TECHNICIAN) RECEIVED

DEC 10 2010

KCC WICHITA

Form CP-23