

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24318-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 16-16S-13W  
4950 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: DEUTSCH Well #: 1  
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W 93 N PO BOX 360  
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	515	0	60/40 POZ 195 SX
PROD	5.5	3369	2219	COMMON 125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/19/2010 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: STEVE BODINE, PRODUCTI Company: DAYSTAR PETROLEUM, INC. Phone: (620) 793-2757

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/19/2010 1:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.  
Cut casing at 2219' - pulled to 1500' - pumped 130 sxs cement with 300# hulls.  
Pulled casing to 1500' - pumped 40 sxs cement with 100# hulls.  
Pulled to 525' - pumped 60 sxs cement.  
Pulled to 150' - circulated cement to surface with 75 sxs cement.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3369			OPEN HOLE

**INVOICED**

DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

**RECEIVED**  
**AUG 25 2010**  
**KCC WICHITA**

Remarks: COPELAND ACID AND CEMENTING-TICKET #34585.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

AUG 23 2010

